



Bruhath Bengaluru Mahanagara Palike, Dasarhalli Zone
Office of the Executive Engineer, Dasarhalli Division.


Schedule - B

Name of the Work : Construction of RCC drains at 7th cross in Santhosh Nagara and other roads in ward no. 13 Shettyhalli sub division					
Sl No	Item Name	Unit	Estimate Quantity	Rate to be Quoted M/s M/s Nischal K Lakshman	
				In Figures (Rs)	In Words (Rs)
1	Earthwork excavation by manual means in ordinary soil involving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods Complete Asper the Directon Of Enggineer -in-charge of the work	CUM	250	175.96	Rupees One Hundred Seventy Five and Ninety Six Paise Only
2	Removing B S Slab Drain And Stacking Asper the Directon Of Enggineer -in-charge of the work	SQM	337.5	65.72	Rupees Sixty Five and Seventy Two Paise Only
3	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing Asper the Directon Of Enggineer -in-charge of the work (Available course aggregates)	CUM	29.78	4000	Rupees Four Thousand Only
4	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing Asper the Directon Of Enggineer -in-charge of the work (Remaining Balance Qty.)	CUM	5.62	5159.02	Rupees FiveThousand and One Hundred Fifty Nine and Two Paise Only



Signature of the Contractor


EXECUTIVE ENGINEER -
Bruhat Bangalore Mahanagara Palike,
Dasarahalli Division, Bangalore-57
Executive Engineer
Dasarahalli Division

Sl No	Item Name	Unit	Estimate Quantity	Rate to be Quoted M/s M/s Nischal K Lakshman	
				In Figures (Rs)	In Words (Rs)
5	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.43cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing Asper the Directon Of Enggineer -in-charge of the work	CUM	91.65	5500.0	Rupees FiveThousand and Five Hundred Only
6	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour Asper the Directon Of Enggineer -in-charge of the work	SQM	900	265.0	Rupees Two Hundred and Sixty Five only
7	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery Asper the Directon Of Enggineer -in-charge of the work	Tonne	5.5	64243.42	Rupees Sixty Four Thousand Two Hundred and Fourty Three and Fourty Two paisa Only
8	Providing & laying reinforced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Asper the Directon Of Enggineer -in-charge of the work	SQM	17.28	1680.0	Rupee One Thousand and Six Hundred and Eighty Only



Signature of the Contractor



Executive Engineer
Dasarahalli Division

Bruhath Bengaluru Mahanagara Palike

Signature of the Contractor

Executive Engineer
Dasarahalli Division